

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No.EE/YNK-D/E-PMT/07/2018-19 Dated: 16-02-2019

APPROVED TENDER SCHEDULE -'B'


Item-09

Name of Work:-Improvements roads and footpath in ward no:02 of Yelahanka Sub division

SI	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAJANNA N	
				Rate	Rate in Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (Page No 143., I.No.19.1 of KPWD S.R 2018-19).	Cum	568.00	233.86	Rupees Two Hundred Thirty Three and Paise Eighty Six Only
2	KSRRB M300- Construction of Embankment with Material Gravel/ Murum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murum, watering charges & compaction by vibratory roller to 95% of proctors density) MORTH Specification No. 305 (Page No 147., I.No.19.60 of KPWD S.R 2018-19).	Cum	373.75	388.08	Rupees Three Hundred Eighty Eight and Paise Eight Only
3	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications. Clause 401 of MORTH V Revision. (Page No 153., I.No.20.5 of KPWD S.R 2018-19).	Cum	149.50	2247.28	Rupees Two Thousand Two Hundred Forty Seven and Paise Twenty Eight Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAJANNA N	
				Rate	Rate In Words
4	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. (Page No 13., I.No.4.3 of KPWD S.R 2018-19).	Cum	149.50	6092.25	Rupees Six Thousand Ninety Two and Paise Twenty Five Only
5	KSRB 14.6 : Providing and laying heavy duty cobble stones interlock pavers, using cement and coarse sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications. Specification No. KBS - do - heavy duty cobble stones -do- 60mm thick (Page No . 103, I.No. 14.6 of KPWD S.R 2018-19).	Sqm	1495.00	1257.38	Rupees One Thousand Two Hundred Fifty Seven and Paise Thirty Eight Only
6	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete (Page No . 27, I.No. 5.30 of KPWD S.R 2018-19).	Nos	722.22	487.19	Rupees Four Hundred Eighty Seven and Paise Nineteen Only
7	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (Page No. 180, I.No. 24.1 of KPWD S.R 2018-19).	Sqm	113.75	95.53	Rupees Ninety Five and Paise Fifty Three Only

Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.